

vgbe-Standard

Construction and installation supervision in the manufacture and assembly of water-tube boilers and associated systems in thermal power plants

VGBE-S-013-00-2026-01-EN

3rd edition

(formerly VGB-S-013-00-2017-04-EN)



vgbe-Standard

Construction and installation supervision in the manufacture and assembly of water-tube boilers and associated systems in thermal power plants

VGBE-S-013-00-2026-01-EN

3rd edition

(formerly VGB-S-013-00-2017-04-EN)

Publisher:

vgbe energy e.V.

Publishing house:

vgbe energy service GmbH

Verlag technisch-wissenschaftlicher Schriften

Deilbachtal 173 | 45257 Essen, Germany

Phone: +49 201 8128-200

E-mail: sales-media@vgb.org

ISBN 978-3-96284-423-3 (print, English)

ISBN 978-3-96284-424-0 (e-book, English)

ISBN 978-3-96284-421-9 (print, German)

ISBN 978-3-96284-422-6 (e-book, German)

All rights reserved, vgbe energy.

www.vgbe.energy | www.vgbe.services

Preface

for the third edition 2026 of the VGBE Standard VGBE-S-013-00-2026-01-EN.

The content of this vgbe-Standard has been reviewed by the vgbe Technical Committee (TC) “Construction and Assembly Supervision/Quality Assurance” and confirmed to be still up to date. The amendment sheet with the following change has been included in the document:

Change: 2025-03-2417

Amended chapter: 5.1.2 Scope of testing

adopted.

The listed norms, standards and other guidelines have been reviewed to ensure that they are still up to date.

Essen, Januar, 2026

vgbe energy e.V.*

* vgbe energy e.V. has been the new name of VGB PowerTech since April 2022.

Notes on the translation

In English-language texts, the “dot” is generally used as the decimal separator with the “comma” as the thousands separator. In graphics originating from the German speaking world, the “comma” character may be used as the decimal separator with the “dot” as the thousands separator.

American English is the main language used in this vgbe-Standard.

Authors

The following persons were involved in the revision of this edition of the vgbe-Standard:

Patrick Kozlowski, Lausitz Energie Kraftwerke AG

Ralf Nothdurft, EnBW Energie Baden-Württemberg AG

Jürgen Hellwig, RWE Power AG

Jens Ganswind-Eyberg, vgbe energy e.V.

Wolfgang Daschütz, Wien Energie GmbH

Thomas Rieger, EVN Wärmekraftwerke AG

Andre Schwarz, Onyx Power

Simon Heckmann, RWE Power AG

Michael Ohme, Berlin Wärme AG

We would take the opportunity here to thank all contributors, whether mentioned by name or not, for their assistance.

This vgbe-Standard VGBE-S-013-00-2026-01-EN has been discussed and agreed with the Fachverband VAIS (Verband für Anlagentechnik und IndustrieService e.V.).

Table of contents

1	General	13
1.1	General observations.....	13
1.2	Options	13
1.3	Scope of applicability	13
1.4	Pressure Equipment Directive (PED) / 14 th German Product Safety Ordinance (ProdSV)	14
1.5	Technical standards.....	15
1.6	Quality assurance	15
1.7	Processing of input materials.....	16
1.8	Manufacturing inspection.....	17
1.9	Non-conformities.....	17
1.10	QA documentation	17
2	Materials	18
3	Welded joints	19
3.1	Requirements for manufacturers	19
3.2	Welders' qualifications	20
3.3	Manual dexterity tests.....	22
3.4	Welding consumables.....	22
3.5	Weld preparation	23
3.6	Preheating	24
3.7	Tacking	25
3.8	Welding.....	25
3.9	Mechanical/chemical post-treatment of weld seams and adjacent areas	26
3.10	Further additions for fabrication to EN 12952	26
3.11	Further additions for fabrication in structural steelwork to EN 1090.....	27
3.12	Construction and installation supervision.....	27
4	Post weld heat treatment	29
4.1	General.....	29
4.2	Heat control for 1.4922, 1.4903, 1.4901 and 1.4915.....	31
4.3	Dispensing with post weld heat treatment	32
4.4	Repairs on heat treated weld seams	32
4.5	Construction and installation supervision.....	32
5	Non-destructive tests on weld seams	33
5.1	Requirements for testing and scope of testing.....	33
5.1.1	Requirements for testing.....	33
5.1.2	Scope of testing.....	34
5.2	Test methods	37
5.2.1	Visual inspection (VT).....	37

5.2.2	Surface examination.....	37
5.2.3	Dye penetrant testing (PT).....	37
5.2.4	Magnetic particle testing (MT)	37
5.2.5	Radiographic testing (RT).....	37
5.2.6	Ultrasonic testing (UT)	38
5.2.7	Hardness testing (HT).....	39
5.2.8	Positive material identification (PMI).....	40
5.3	Test documentation	40
5.4	Construction and installation supervision.....	41
6	Manufacturing in the workshops.....	42
7	Processing of tube material.....	43
7.1	General.....	43
7.2	Tube bends.....	43
7.2.1	Bending of tubes.....	43
7.2.2	Post bending heat treatment.....	44
7.2.3	Out-of-roundness (departure from circularity).....	44
7.2.4	Ripples.....	45
7.2.5	Ball passage test	47
7.2.6	Construction supervision	48
7.3	Tubes with non-pressure-retaining welded-on parts.....	49
7.3.1	Tubes with welded-on supports and fins.....	49
7.3.2	Tubes with welded-on studs	49
7.3.2.1	Arrangement.....	49
7.3.2.2	Boiler studs (general).....	50
7.3.2.3	Welding technique	50
7.3.2.4	Preheating and post weld heat treatment.....	51
7.3.2.5	Notes on the work.....	51
7.3.2.6	Construction supervision	51
7.4	Membrane tube walls.....	52
7.4.1	Construction supervision	54
7.5	Die-forged parts connecting tubes	55
7.5.1	General.....	55
7.5.2	Construction supervision	55
8	Tube connections.....	56
8.1	Expanded connections and roller-expanded and welded joints on tubes in boiler drums	56
8.1.1	General.....	56
8.1.2	Scope of application	56
8.1.3	Preparation	56
8.1.4	Insertion of the tubes	56

8.1.5	Initial expansion.....	57
8.1.6	Final expansion.....	57
8.1.7	Post-welding expansion.....	57
8.2	Welded joints, nipples and nozzles on boiler drums, headers and separator vessels.....	57
8.2.1	General.....	57
8.2.2	Bores in headers, separator vessels and drums.....	58
8.2.3	Nipples and nozzles.....	58
8.2.4	Welding of nipples and nozzles.....	58
8.2.5	Welding on of dished or flat ends to nozzles, nipples and headers.....	59
8.2.6	Construction supervision.....	59
9	Boiler drums.....	61
9.1	General.....	61
9.2	Ends.....	61
9.3	Internals.....	62
9.4	Construction supervision.....	63
10	Spray attemperators.....	65
10.1	General.....	65
10.2	Construction and installation supervision.....	65
11	Fittings.....	67
11.1	General.....	67
11.2	Design and manufacture.....	67
11.3	Construction supervision.....	67
12	Economizers.....	68
12.1	General.....	68
12.2	Construction supervision.....	68
13	Air preheaters.....	69
13.1	General.....	69
13.2	Design and manufacture.....	69
13.3	Materials.....	69
13.4	Construction supervision.....	70
14	Air and flue gas ducts, dampers and flow measuring equipment.....	72
14.1	General.....	72
14.2	Design and manufacture.....	72
14.3	Construction supervision.....	74
15	Expansion joints.....	75
15.1	Construction supervision.....	75

16	Suspension mountings, openings and fastenings in water-tube boilers	76
16.1	Design and manufacture.....	76
16.2	Materials	76
16.3	Construction supervision	77
17	Supporting steelwork for boiler, bunker and air preheater	78
17.1	General.....	78
17.2	Materials and semi-finished products	78
17.3	Surface quality	80
17.4	Test certificates.....	80
17.5	Material traceability.....	81
17.6	Material marking during working	81
17.7	Material cutting	81
17.8	Straightening work.....	81
17.9	Tests on weld seams	83
17.10	Measurement.....	84
17.10.1	General.....	84
17.10.2	Checks required during and after manufacture.....	88
17.10.2.1	Columns; straightness and connection of horizontal members.....	88
17.10.2.2	Column heights.....	88
17.10.2.3	Horizontal members.....	88
17.10.3	Collation of the records.....	88
17.10.4	System centre.....	90
17.10.5	Tolerances.....	92
17.11	Construction supervision	95
18	Platforms, steps, ladders and pedestals	97
18.1	General.....	97
18.2	Construction supervision	97
19	Fans	98
19.1	General.....	98
19.2	Materials	98
19.3	Construction and installation supervision.....	98
20	Cladding	100
20.1	Area of application	100
20.2	Manufacturer's qualifications	100
20.3	Welders' qualifications	100
20.4	Welding consumables.....	100
20.5	Weld procedure specification.....	100
20.6	Surface quality	101

20.7	Minimum wall thickness of the tubes to be hard faced.....	101
20.8	Tube wall cladding thickness measurement	101
20.9	Degree of dilution.....	101
20.10	Visual inspection.....	101
20.11	Surface testing.....	102
20.12	Ferritic contamination	102
20.13	Construction supervision	102
21	Shipment to site.....	103
21.1	General.....	103
21.2	Incoming goods inspection	103
21.3	Storage of the components.....	103
22	Erection and installation at site.....	105
22.1	General.....	105
22.2	Quality assurance	105
23	Installation of the supporting steelwork for the boiler, bunker and air preheater.....	107
23.1	General.....	107
23.2	Measurement.....	108
23.2.1	Conditions, measuring equipment and records	108
23.2.2	Checks required during installation.....	108
23.2.3	Tolerances (Figure 23-3 and Figure 23-4).....	111
23.3	Installation supervision	114
24	Installation of platforms, steps, ladders and pedestals	115
24.1	General.....	115
24.2	Notes on installation	115
24.3	Construction supervision	115
25	Installation of firing systems	117
25.1	General.....	117
25.2	Installation supervision	117
26	Assembly and installation of the boiler parts	118
26.1	General.....	118
26.1.1	Installation supervision	118
26.2	Drum installation.....	118
26.2.1	General.....	118
26.2.2	Installation supervision	119
26.3	Installation of headers, vessels, superheated steam coolers, safety valves and venting lines	119
26.3.1	Fixed installation	119

26.3.1.1	Fitting the safety valves	120
26.3.1.2	Fitting the venting and drainage lines	120
26.3.2	Movable installation	120
26.3.3	Vertical installation.....	121
26.3.4	Installation supervision	121
26.4	Installation of tubes, tube coils and tube walls.....	122
26.4.1	Connecting pipes.....	122
26.4.2	Tube walls	122
26.4.3	Top casing tubes, top casing tube walls and partition walls.....	123
26.4.4	Supporting tubes.....	123
26.4.5	Tube coils	123
26.4.6	Bulkheads.....	124
26.4.7	Installation supervision	124
27	Installation of air preheaters.....	125
27.1	Regenerative air preheaters	125
27.1.1	Air preheater with rotating or stationary storage mass carrier	125
27.2	Steam-heated air preheaters	125
27.3	Installation supervision	126
28	Installation of air and gas ducts, dampers, flow measuring equipment and expansion joints.....	127
28.1	Air and gas ducts	127
28.2	Installation supervision	127
28.3	Dampers and flow measuring equipment	127
28.4	Installation supervision	128
28.5	Expansion joints.....	128
28.6	Installation supervision	129
29	Leakage test with air;	130
30	Hydrostatic pressure testing of the steam generator (boiler pressure test)	131
30.1	Basis.....	131
30.2	Conditions for the pressure test.....	131
31	Internal cleaning of the pressure vessel	132
32	Insulating work and plate cladding	133
32.1	General.....	133
32.2	Properties and application of insulating materials.....	133
32.3	Pins for fastening of insulating material mats	134
32.4	Substructure at boiler walls and buckstays for fastening of the trapezoidal sheet cladding	134

32.5	Boiler buckstays.....	134
32.6	Sheet metal cladding and jacketing	135
32.7	Pipelines	135
32.8	Support and load-bearing structure for pipelines	136
32.9	Jackets of galvanized steel or aluminium sheet for valves	137
32.10	Substructures on header front ends and dead spaces	137
32.11	Shielding of bellows-type and soft material expansion joints	137
32.12	Flue gas duct ties.....	138
32.13	Access doors in flue gas and air ducts	138
32.14	Installation supervision	138
33	Literature	140
34	Abbreviations.....	147
35	Tables	150
36	Figures.....	151